

A-align Technical Manual

Rusticated
Weatherboard

A-align[®]
by claymark




BRANZ Appraised
Appraisal No. 637 [2017]
Appraisal No. 638 [2017]

 **claymark**[®]

Ingrained Precision

in everything we do

claymark.co.nz

A-align® by Claymark aligns natural sustainable timber to modern design needs combining striking good looks with guaranteed high performance.

- ✓ From Renewable Wood
- ✓ Primed & Undercoated
- ✓ **BRANZ** Appraised
- ✓ System Solution
- ✓ **NZBC** Compliant
- ✓ Fast Install & Less Waste



Renewable natural pine

The NZ radiata pine used in the A-align timber cladding system solution is from renewable and sustainable plantation resources.

It is a remarkably versatile timber renowned for exceptional machining properties, durability and lightness.

Once finger-jointed they form products that exceed the pine's original physical and structural characteristics by over 400%.

This makes it a brilliant natural 'environmentally friendly' construction choice over alternative building materials made from non-renewable fossil fuels.



Brnz Impact Test

Impact resistance is a key criteria for cladding materials being used in the construction of schools and similar light commercial buildings not exceeding 10 metres in height. To meet regulatory and specifier requirements, A-align timber weatherboards (18mm thick) were subjected to hard body high impact resistance tests performed by BRANZ. High density fibre cement weatherboard (16mm thick) were also included in these tests. A-align timber weatherboard performed significantly better than the fibre cement weatherboard and, although the level of damage caused to both was small, the fibre cement weatherboard had a greater depth of ball indentation.

Independently assessed

A BRANZ Appraisal is a comprehensive independent assessment of building products and systems for fitness for purpose and Building Code compliance.

The A-align timber cladding system solution has been vigorously assessed from manufacturing processes, through to fitness for purpose, durability, weather-tightness performance and structural capability over a drained and vented cavity.

Contents

A-LIGN COMPONENTS	2	10.7 External mitred corners	10
A-LIGN NAILING SCHEDULE	3	10.8 Internal corners	10
INTRODUCTION	4	11.0 Window and door openings	10
SPECIFICATIONS FOR EXTERIOR CLADDING	5	11.1 Aluminium windows	10
1.0 Before application of the cladding	5	11.2 Timber windows	10
2.0 A-align rusticated weatherboard	5	11.3 Flashings	10
2.1 A-align rusticated weatherboard sizes	5	11.4 A-align facings	11
2.2 A-align timber accessories	5	11.5 Air seals	11
2.3 Accessories by Quickflash	5	12.0 Painting A-align	11
3.0 Detailing	5	12.1 Materials	11
4.0 A-align on site	5	12.2 Painting	11
4.1 Storage	5	13.0 General information	11
4.2 Handling	6	13.1 Handling	11
5.0 Wall underlays	6	13.2 Installation	11
5.1 Non-rigid underlays	6	13.3 Finishing	12
5.2 Rigid underlay installation	6	13.4 Moisture	12
5.3 Building wrap installation	6	13.5 Heat generating colours	12
5.4 Synthetic wall wrap installation	7	14.0 Building maintenance	12
6.0 Flashings	7	14.1 New construction	12
6.1 Supply	7	14.2 Regular washing	12
6.2 Materials	7	14.3 Maintenance painting	12
6.3 Fabrication and installation	7	CLAYMARK A-LIGN WARRANTY	13
7.0 Sealants	7	DRAWINGS DIRECTORY	14
7.1 Materials	7	SET OUT GUIDES	17
8.0 Air Seals	8	3-DIMENSIONAL DIAGRAMS	20 – 28
8.1 Materials	8	CAD DRAWINGS – direct fixed	29 – 53
8.2 Installation	8	CAD DRAWINGS – cavity fixed	54 – 79
9.0 Drained and vented cavities	8	CLAYMARK – WARRANTY	80
9.1 Design	8		
9.2 Materials	8		
9.3 Fixing A-align battens	8		
9.4 Cavity closure	9		
10.0 Fixing A-align rusticated weatherboard	9		
10.1 Fixings	9		
10.2 Fixing method	9		
10.3 Setting out	9		
10.4 Fixing procedure for rusticated weatherboard	9		
10.5 Joining weatherboard	10		
10.6 External box corners	10		

Components

H3.1 – Primed and Undercoated

A-lign Components*	Item #	Size	Length	Profile
A-lign Rusticated Weatherboard	04671	142 x 18mm	6.1 metres	
A-lign Rusticated Weatherboard	04683	142 x 18mm	7.2 metres	
A-lign Rusticated Base Board	04677	142 x 18mm	6.1 metres	
A-lign Rusticated Weatherboard	04674	187 x 18mm	6.1 metres	
A-lign Rusticated Weatherboard	04686	187 x 18mm	7.2 metres	
A-lign Rusticated Base Board	04680	187 x 18mm	6.1 metres	
A-lign Cavity Batten (structural)	04563	45 x 19mm	5.4 metres	
A-lign 142 Rusticated Pre-cut Scriber (for 142 x 18)	04658	27 x 18mm	5.4 metres	
A-lign 142 Rustic. Transition Scriber (for 142 x 18)	04697	42 x 27mm	5.4 metres	
A-lign 142 Rustic. Transition Scriber (for 142 x 18)	04698	66 x 18mm	5.4 metres	
A-lign 187 Rusticated Pre-cut Scriber (for 187 x 18)	04661	27 x 18mm	5.4 metres	
A-lign 187 Rustic. Transition Scriber (for 187 x 18)	04699	42 x 27mm	5.4 metres	
A-lign 187 Rustic. Transition Scriber (for 187 x 18)	04700	66 x 18mm	5.4 metres	
A-lign 142 Rustic. Internal Scriber (for 142 x 18)	04666	27 x 27mm	5.4 metres	
A-lign 187 Rustic. Internal Scriber (for 187 x 18)	04655	27 x 27mm	5.4 metres	
A-lign Weatherhead and Sill Mould	04595	42 x 30mm	5.4 metres	
A-lign Rusticated Scalloped Filler Mould	04689	50 x 9mm	5.4 metres	
A-lign Eaves Mould	04576	42 x 18mm	5.4 metres	
A-lign Facing (grooved)	04573	42 x 18mm	5.4 metres	
A-lign Facing (double grooved)	04603	66 x 18mm	5.4 metres	
	04606	90 x 18mm	5.4 metres	
	04609	116 x 18mm	5.4 metres	
	04612	138 x 18mm	5.4 metres	
	04615	185 x 18mm	5.4 metres	
A-lign Pre-fabricated Box Corner	04592	102 x 102 x 18mm	5.4 metres	

Nailing Schedule

Description Profile	Timber Size (mm)	Nail Size	Specification Clause
A-align Rusticated Direct Fixed Weatherboard	142 x 18 / 187 x 18	60 x 2.80 hot dipped galv* jolt head	10.1 and 10.2
A-align Rusticated Cavity Fixed Weatherboard	142 x 18 / 187 x 18	60 x 2.80 hot dipped galv* jolt head 75 x 3.15 mm hot-dip galvanised or stainless steel ring shank jolt head nails for NZS 3604 Wind Zone Extra High, and specific design wind pressures up to and including design differential 2.5kPa ULS.	10.1 and 10.2
A-align Cavity Batten (structural)	45 x 19	60 x 2.80 hot dipped galv* or stainless steel ring shank Jolt head hand driven	9.3
		64 x 2.80 hot dipped galv* gun driven / 65 x 2.87 stainless steel ring shank gun driven	9.3
A-align Rusticated Pre-cut Scribe	36 x 18	60 x 2.80 hot dipped galv* jolt head	10.6
A-align Rusticated Internal Corner Scribe	27 x 27	60 x 2.80 hot dipped galv* jolt head	10.8
A-align Weatherhead and Sill Mould	42 x 30	60 x 2.80 hot dipped galv* jolt head	
A-align Rusticated Scalloped Filler Mould	50 x 9	30 x 2.50 hot dipped galv* flat head/clouts	
A-align Eaves Mould	42 x 18	60 x 2.80 hot dipped galv* jolt head	
A-align Grooved Facing	All sizes	50 x 2.50 hot dipped galv* jolt head	11.4
A-align Prefabricated Box Corner	102 x 102	50 x 2.50 hot dipped galv* jolt head	10.6
Quickflash Flashings	All sections	30 x 2.50 hot dipped galv* flat head/clouts	2.3, 6.1 and 9.4

* In sea spray zones (refer to NZS 3604 paragraph 4.2.3) all fixings must be type 316 stainless steel.

Introduction



Scope

The A-lign Timber Cladding Solution can be used for the cladding specification of light commercial and domestic buildings where the:

- Building is within the scope of NZS 3604 timber framed buildings and E2/AS1.
- Building height does not exceed 10 metres.
- Building is situated within NZS 3604 Building Wind Zones up to, and including 'Extra High'.
- Cladding solution uses the Timber A-lign accessories and Quickflash flashings given in this specification.
- Building has A-lign rusticated weatherboard installed over a drained and vented cavity where the E2/AS1 risk score exceeds 6.

Note: The A-lign Timber Cavity Cladding Solution can also be used for cladding timber framed buildings subject to specific design, up to a design differential ultimate limit state (ULS) wind pressure of 2.5 kPa.

These specifications:

- Cover the installation of A-lign rusticated weatherboard as a complete cladding solution following the details given in this document and associated CAD files.
- Must be made specific to each building project by including only those clauses that apply and omitting those that do not apply.
- Are written as direct instructions to the contractor (it does not make use of the words 'should' or 'shall') and this format must be adhered to.

Note: The success of the cladding solution is partially dependent on the stability and accuracy of the framing which must meet the minimum standards set by NZS 3604.

Note: The 3-Dimensional diagrams and CAD drawings in this manual are current at the date of this manual (Sept 2018). For any amendments or updates to these diagrams or drawings, please refer to our web site: www.claymark.com/triptech/a-lign-nail-fix-cad-details

— Specifications for exterior cladding

1.0 Before application of the cladding

Before beginning installation of the A-align Timber Cladding Solution ensure that:

- The framing complies with the requirements of NZS 3604 timber framed buildings.
- The framing is straight and within the tolerances allowed by Table 2.1 Tolerances of NZS 3604.
- The moisture content of the framing timber does not exceed 20%.
- Additional studs are included at internal corners where there is a cavity.
- The wall underlay complies with the requirements of Table 23 E2/AS1 and is installed in accordance with Section 5.0–5.4 of this specification.
- Window and meter box openings are framed out to give a 7.5mm minimum clearance between the reveal or window frame and the trimmed opening (5mm minimum finished clearance when window installed).

2.0 A-align weatherboard

2.1 Rusticated weatherboard sizes

- 142 x 18mm
- 187 x 18mm

Lengths 6.1m and 7.2m

Rusticated base board sizes

- 142 x 18mm
- 187 x 18mm

Lengths 6.1m (7.2m by arrangement)

2.2 A-align timber accessories

Note: A-align accessories are finger-jointed, treated to H3.1 and primed and undercoated. The A-align cavity batten is treated but not painted.

- A-align prefabricated 102 x 102mm box corner in 5.4m lengths.
- A-align pre-cut 27 x 27mm internal corner scribe pencil edge in 5.4m lengths.
- A-align pre-cut 42 x 27mm and 66 x 18mm transition scribes with pencil edge in 5.4m lengths.
- A-align facing boards – available in 42, 66, 90, 116, 138, 185 x 18mm thickness in 5.4m lengths.
- A-align rusticated scalloped filler mould – in 5.4m lengths.

- A-align structural cavity batten – 45 x 19mm in 5.4m lengths.
- A-align bevelled soffit eaves mould – 42 x 18mm in 5.4m lengths.
- A-align weatherhead and sill mould – 42 x 30mm in 5.4m lengths.

2.3 Accessories by Quickflash

Use of Quickflash flashings are an integral part of the A-align cladding system as defined in the CAD drawings. Select the flashings required.

3.0 Detailing

A-align rusticated weatherboard CAD details and computer generated 3-Dimensional construction diagrams are contained in the full A-align technical manual.

4.0 A-align on site

Arrange for delivery of A-align timber weatherboards just prior to being required.

4.1 Storage

Note: Correct storage of weatherboards on site is critical.

A-align weatherboards, structural cavity battens and accessories have been machined to fine engineered tolerances from finger-jointed clear wood base material with an equilibrium moisture content of 11% plus or minus 2%. If A-align weatherboards, structural cavity battens and accessories are exposed to moisture before installing, as wood is hygroscopic and primers do not prevent moisture uptake, some dimensional swelling will occur and the ease of the system installation will be impaired. Correct storage of the weatherboards, battens and accessories is critical for ease of installation.

Store weatherboards

On a firm level base with timber supports at not greater than 900mm centres. Clear of the ground by a minimum of 150mm under cover and protected from sun and rain.

Where A-align weatherboards are delivered with factory packing, keep the packing and store as described.

To ensure product remains dry provide a secondary cover. Weatherboards should be stored indoors where practical to provide total weather protection.

Specifications for exterior cladding

4.2 Handling

Do not tip the weatherboards from a truck. Either use a mechanical lifting device or unload the weatherboards by hand.

Do not drag weatherboards across the ground.

Always carry individual weatherboards with their long section vertical to avoid excessive bending.

5.0 Wall underlays

Note: A wall underlay is any material placed on the framing and behind the cladding to act as a second line of weathering defence.

Note: The selected wall underlay must have a serviceable life of at least 50 years.

Wall underlays include flexible materials, such as Kraft based papers or synthetic wraps, and rigid sheathings such as plywood or fibre cement board.

Wall underlays suitable for use with the A-lign Timber Cladding Solution are those meeting the requirements of Table 23 of E2/AS1.

5.1 Non-rigid underlays

Note: Specify the actual name/insert specific manufacturer/product of underlay you wish to have installed and select the specific installation instructions.

A wall underlay complying with the requirements of E2/AS1 Table 23 must be installed to the outer face of the wall framing.

Select one option from the following:

- Fire retardant Kraft paper (insert specific manufacturer/product).
- Heavyweight bitumen soaked Kraft paper (insert specific manufacturer/product).
- Absorbent synthetic wall wrap (insert specific manufacturer/product).
- Non-absorbent synthetic wall wrap (insert specific manufacturer/product).

For buildings with other than flush-stopped sheet internal linings or areas of unlined wall, the wall underlay must meet the air-tightness requirement of E2/AS1 Table 23.

Openings for windows, doors and meter boxes must have the opening trimmed with flexible flashing tape compatible with the wall underlay, as required by details in E2/AS1.

5.2 Rigid underlay installation

Note: Specify the rigid sheathing or rigid air barrier material to be used.

Support all rigid sheet edges with framing.

Fix in accordance with the sheet manufacturers instructions.

Use hot-dip galvanised fixings, except for bracing and sea spray zones where stainless steel fixings must be used.

Fit PVC or butyl 'Z' flashings along all horizontal joints of the rigid sheathing.

Fix rigid sheathing in place with sufficient fixings to resist wind loading (the sheathing will be finally held in place by the cladding fixings).

5.3 Building wrap installation

Note: Select to suit the underlays.

Lay the Kraft-based building paper horizontally across the framing members with a minimum 150mm overlap at all joints.

Run material continuously around internal and external corners – do not join material at corners.

Install taut and ensure that there are no creases in the building paper.

Fix with clips or staples and tape in accordance with the building paper manufacturer's instructions.

Turn wall underlay into the framing all round windows, doors and meter box openings and tape the 'V' cut corners and the full width of the sill trimmer with compatible flexible flashing tape.

Cover the wall from bottom to top plate.

Repair all holes or tears in the building paper before commencing cladding installation. Ensure the building paper has not been exposed to the weather for more than the time allowed by the wrap manufacturer.

For installation under cavity battens install horizontal strips of plastic tape at 300mm centres and staple to the framing to prevent bulging where batten spacing exceeds 450mm centres.

5.4 Synthetic wall wrap installation

Lay the synthetic wall wrap horizontally across the framing members with a minimum 150mm overlap at sheet joints.

Run material continuously around internal and external corners – do not join material at corners.

Install taut and ensure that there are no creases in the wrap and use fixings that will resist tearing under wind loads.

Fix with clips or staples and tape in accordance with the synthetic wrap manufacturer's instructions.

Turn wrap edges into the framing all round windows, doors and meter box openings and tape the 'V' cut corners and the full width of the sill trimmer with compatible flexible flashing tape.

Cover the wall from bottom to top plate.

Repair all holes or tears in the wrap before commencing cladding installation.

Ensure the synthetic wrap has not been exposed to the weather for more than the time allowed by the wrap manufacturer.

For installation under cavity battens install horizontal strips of plastic tape at 300mm centres stapled to the framing to prevent bulging where batten spacing exceeds 450mm centres.

6.0 Flashings

Note: Flashings as noted on the construction details must be provided and may be made from either sheet steel with a galvanized or zinc/aluminium alloy coating, aluminium or from stainless steel. They may be factory pre-finished if required. Refer to NZS 3604 section 4 or E2/AS1 Table 20 for durability requirements.

6.1 Supply

Flashings for use with the A-align Timber Cladding Solution are those manufactured by Quickflash as detailed in the CAD drawings.

Where the A-align cladding abuts a different cladding use flashings as shown in the A-align CAD details.

Aluminium window head flashings are the responsibility of the window supplier.

6.2 Materials

Note: Select the appropriate material for the environment.

Select the flashing material from:

- 0.55 BMT galvanised sheet steel.
- 0.55 BMT zinc/aluminium alloy coated.
- 0.55 BMT galvanised sheet steel factory coated.
- 0.55 BMT zinc/aluminium alloy coated factory coated.
- 316 grade stainless steel.
- 0.9mm powder-coated aluminium for window head flashings – window head flashing by window supplier.

6.3 Fabrication and installation

Flashings must be machine bent accurately to the detailed profile.

Where necessary, site-cut each flashing to suit each circumstance and form stop-ends where appropriate.

Fix flashings using compatible fixings and ensure that the building wrap is installed as shown in the A-align CAD details.

Isolate zinc/aluminium alloy coated steel, galvanised steel and uncoated aluminium flashings from timber treated with copper-based treatments with a layer of kraft paper wall underlay.

7.0 Sealants

Note: Sealants are used to assist with weathering at joints and laps. Sealants must not be relied on for primary weather protection.

7.1 Materials

Sealant suitable for use with the A-align Timber Cladding Solution is a (specify brand/ manufacturer) sealant complying with E2/AS1 or a sealant covered by a valid BRANZ Appraisal used in accordance with the manufacturer's instructions.

Specifications for exterior cladding

8.0 Air seals

Note: Air seals are an essential element of the air barrier component of the cladding solution. They complete the air barrier by sealing between the building wrap and the door and window reveals and meter boxes. The air seal is formed by applying sealant over a backing rod to which the sealant will not bond or by using self-expanding polyurethane foam over a backing rod.

8.1 Materials

Backing rod: closed cell PEF rod of a diameter to suit the gap.

Air seal: acrylic latex or modified silicon sealant complying with ISO 11600 used in accordance with the manufacturer's instructions or low expansion self-expanding polyurethane foam in accordance with the requirements of E2/AS1.

8.2 Installation

Insert the backing rod into the gap between the window reveal/meterbox and the trim framing to the perimeter of the opening. Press in approximately 15mm. Apply the sealant/expanding foam. Trim off excess material.

9.0 Drained and vented cavities

Note: For designs following E2/AS1 a drained and vented cavity is required behind rusticated weatherboards when the weathertightness risk score for that building face exceeds 6. The cavity is formed by fixing A-lign treated battens over the studs. A-lign cavity battens are to be structurally fixed in accordance with BRANZ Bulletin 582. Vermin proofing, which allows draining and ventilation, must be fitted to the bottom of the cavity.

9.1 Design

The cavity must be open to the exterior at the bottom of every second storey and across the tops of windows, doors and other penetrations such as meter boxes. Fit Quickflash cavity closures to prevent vermin entry.

9.2 Materials

Structural battens: A-lign structural cavity battens – 45 x 19mm are treated to H3.1.


Cavity closure: zinc/aluminium alloy coated steel, aluminium or stainless steel supplied by Quickflash with a minimum ventilation area of 1000mm² per lineal metre of wall.

9.3 Fixing A-lign battens

Note: Refers to the fixing of A-lign structural cavity battens, over wall underlay, to the wall studs. This allows the A-lign rusticated weatherboard to be fixed directly to the cavity battens eliminating the need for larger fixings (refer 10.1 fixings).

Fix batten as follows:

- Over framing members.
- With a gap between battens at corners and below windows. Note that battens must be kept at least 100mm away from the line of the trimmed opening below windows.



- Where penetrations of the wall cladding (other than windows) are wider than the cavity batten spacing, allowance must be made for air flow between adjacent cavities by leaving a minimum 10mm gap between the bottom of the vertical cavity batten and the flashing to the opening.
- With no continuous horizontal battens below windows.
- Vertical battens continuous past the ends of head flashings.
- Fix A-align structural cavity battens over wall underlay to studs with 60 x 2.80 hot dipped galvanised or stainless steel ring shank jolt head hand driven. 64 x 2.80 hot dipped galvanised gun driven/65 x 2.87 stainless steel ring shank gun driven at 300mm centres. Stagger fixings 12mm either side of the batten centre line.

9.4 Cavity closure

Fit continuous Quickflash cavity closure trim to the bottom of all cavities, including across the tops of openings to prevent vermin entry. Fix with 30 x 2.50mm galvanised flat head nails/clouts at 400mm centres.

10.0 Fixing A-align rusticated weatherboard

Note: Select the appropriate fixings for the installation – whether direct fix or over A-align structural cavity battens.

Note: In sea spray zones (refer to NZS 3604 paragraph 4.2.3) all fixings must be type 316 stainless steel. Hot-dip galvanising must meet the requirements of AS/NZS 4680:2006.

10.1 Fixings

A-align rusticated weatherboard fixings over structural cavity battens (Timber Frame): 60 x 2.8mm hot-dip galvanised or stainless steel ring shank jolt head nails for NZS 3604 Wind Zones up to and including Very High, or 75 x 3.15 mm hot-dip galvanised or stainless steel ring shank jolt head nails for NZS 3604 Wind Zone Extra High, and specific design wind pressures up to and including design differential 2.5 kPa ULS.

Note: Nails must penetrate structural framing by a minimum of 35mm. Where structural battens are used the batten is part of the minimum 35mm penetration.

10.2 Fixing method

Note: Hand nailing is recommended by Claymark. Some gun driven fixings may bruise the surface. If the builder asks to use them it is important that they be tested to make sure that they do not damage the finished surface.

A check should also be made as to the adequacy of the galvanised coating. Claymark endorses the use of the Paslode JoltFast weatherboard nailing system using the appropriate nailing specification.

Note: It is important to use only one fixing per board per stud to allow for movement.

Fix each board with one nail per board at every stud or batten, locate fixing 40mm above the bottom edge of the overlap board to allow for expansion and contraction.

Start fixing weatherboards near the middle of the board and work outwards to the ends.

Pre-drill for fixings if within 50mm of the end of the board.

Punch all nails 2mm below the face of the board.

10.3 Setting out

Note: Movement across the width of A-align rusticated weatherboards is not restricted by board rebates.

Minimum lap for rusticated weatherboards: 25mm.

Use A-align pre-cut scribe as a storey-rod to locate the position of each successive board to ensure that scribes will fit accurately to weatherboards. Keep dry for consistent measurement accuracy.

10.4 Fixing procedure for rusticated weatherboards

Establish the position of the bottom weatherboard or base board to give a minimum overlap of 50mm below the bottom plate or bearer.

Fix the A-align rusticated base board in place.

Use A-align rusticated scalloped filler mould where necessary for solid backing.

Cut the final board to fit to the soffit.

Specifications for exterior cladding

10.5 Joining weatherboard

Fix weatherboards in full wall lengths where possible. Make joints where unavoidable over studs or battens. Scarf the joint at 45° and use one fixing through the overlapping board.

Prime the cut-ends of scarf joints with End Seal aerosol primer, or with two coats of premium timber primer before fixing. Allow to dry between coats.

10.6 External box corners

Fit A-align prefabricated 102 x 102 x 18mm external box corner with a minimum of 50mm cover over the weatherboards and fix with two, 50 x 2.50mm galvanised jolt head nails.

Locate the fixings 40mm above the bottom edge of the overlap:

- 468mm centres for 142mm weatherboards (4 laps).
- 486mm centres for 187mm weatherboards (3 laps).

Fit an A-align pre-cut 18mm scribe over the weatherboards, tight against the box corner and fix through pre-drilled holes with 60 x 2.80mm galvanised jolt head nails at 400mm centres.

10.7 External mitred corners

Prime the cut-ends of scarf joints with End Seal aerosol primer, or with two coats of premium timber primer before fixing. Allow to dry between coats.

Install:

- A 65 x 65mm Quickflash hemmed angle back flashing as detailed directly over the wrap.
- Join the weatherboards with a tightly fitting 45° mitre joint.

10.8 Internal corners

Install a 65 x 65mm Quickflash hemmed angle back flashing over the wrap.

Scribe and notch alternate weatherboards or use the A-align pre-cut 27 x 27mm internal corner double scribe.

Prime the cut-ends of scarf joints with End Seal aerosol primer, or with two coats of premium timber primer before fixing. Allow to dry between coats.

11.0 Window and door openings

Note: The integrity of the junctions at the interface of the cladding and the window and door openings is a vital part of the weatherproofing system. Care must be taken to ensure that the work is carried out correctly and that all flashings, weatherings and air seals are in place.

Note: This specification applies to the use of aluminium windows and doors that are in accordance with E2/AS1 paragraph 9.1.10. Use of bi-fold, sliding or other non-hinged windows and doors and timber windows and doors must be submitted to the Building Consent Authority as an Alternative Solution to NZBC Clause E2/AS1.

11.1 Aluminium windows

Aluminium windows installed into an A-align Timber Cladding Solution must:

- Comply with NZS 4211 for the building location.
- Have a minimum 10mm flange covering the weatherboard trim.
- Incorporate scribes to the flange.
- Include a full width sill tray for direct fixed. Cavity fix requires window support bars for trim opening wider than 600mm. Refer to E2/AS1 – 9.1.10.5.
- Have window trimmed openings constructed as shown in E2/AS1 with flexible flashing tapes and air seals.

11.2 Timber windows

Note: Timber windows within a weatherboard cladding is not covered by E2/AS1 and must be consented by a BCA as an Alternative Solution.

Timber windows installed into an A-align Timber Cladding Solution must:

- Have profiles in accordance with NZS 3610.
- Incorporate facings and scribes.
- Incorporate full width sill tray flashings.
- Have window trimmed openings constructed as shown in E2/AS1 with flexible flashing tapes and air seals.

11.3 Flashings

Flashing material and fabrication in accordance with section 6.0 of this specification. Stop-ends to finish at back of cladding.

Head flashings must have:

- 10mm stop-ends when used with a 20mm cavity.
- 15° cross fall.
- 10mm min cover to the window flange.
- 50mm min back upstand to give 35mm min cladding cover.

Fit sill flashing as detailed with stop-ends to all windows.

Sill flashings must have:

- A 5° cross fall.
- 35mm cladding cover at front downturn.
- 20mm stop-ends.
- A 5mm turn up to the back edge.

11.4 A-align facings

Fit A-align grooved facings with a minimum of 50mm cover over the weatherboards and fix with two, 50 x 2.50mm hot dipped galvanised jolt head nails.

Locate the fixings above the lap of the weatherboard at:

- 468mm centres for 142mm weatherboards (4 laps).
- 486mm centres for 187mm weatherboards (3 laps).

Fit A-align pre-cut 18mm scribe over the weatherboards, tight against the facing and fix through pre-drilled holes with 60 x 2.80mm hot dipped galvanised jolt head nails at centres as above.

11.5 Air seals

On completion fit air seals around all window and door openings as specified.

12.0 Painting A-align

12.1 Materials

A premium factory applied primer and undercoat has been applied in two separate coats. Site prime all bare timber surfaces and cut-ends with End Seal aerosol primer, or with two coats of premium timber primer before fixing. Allow to dry between coats.

Finishing coats: 100% premium acrylic house paint (insert specific manufacturers product) as specified in Parts 7, 8, 9 and 10 of AS 3730.

12.2 Painting

Note: Resin bleed may occur from timber in hot conditions or where painted in dark colours. Adherence to the above specification will help minimize the problem.

Note: Primers cannot withstand exposure to weather for extended periods.

Note: Using light colours lessens the chance of distortion by reducing solar heat build up in the weatherboards.

Carry out all painting work in accordance with the appropriate clauses of AS/NZS 2311 Guide to Painting of Buildings.

Finishing coats to be applied after installation of the exterior sheathing, joinery and trim.

Prior to applying finishing coats ensure no moisture related dimensional swelling is evident by measuring profiles against original profile sizes. If swelling is present, delay finish coating until the timber profiles have returned to their original machined sizes.

Fill all nail holes with an exterior grade filler, sand to a smooth surface and spot-prime filled areas and wherever the coating is damaged.

Apply a minimum of two full coats of 100% premium acrylic house paint with a gloss level of 10% and a Light Reflective Value of 45% or greater (ASTM C1549 or ASTM E903).

13.0 General information

13.1 Handling

Store the product where it is dry and kept off the ground using bearers. If stored outside use a secondary waterproof cover but allow for good air circulation. When handling, take care to avoid any damage to surfaces.

13.2 Installation

Avoid scratching or marking of the board during installation and cutting. Prime the cut-ends of scarf joints with End Seal aerosol primer, or with two coats of premium timber primer before fixing. Allow to dry between coats.

Specifications for exterior cladding

13.3 Finishing

Remove all loose material, dirt etc. Spot prime exposed bare timber with selected premium timber primer, putty all nail holes, use a filler and sealants nominated as exterior type suitable for overcoating with 100% acrylic paint. Apply a minimum of two coats of 100% premium acrylic house paint as per instructions on the container.

13.4 Moisture

Tannin extracts (dark stains in the film) are a result of the board being allowed to get wet. This is neither a board nor paint issue as it is a result of excessive moisture, which infiltrates the board through not following these guidelines. After installation of the board it is recommended that the painter be allowed to complete the finishing work as soon as practical. Refer to 12.2 Painting.

13.5 Heat generating colours

Dark colours absorb heat from the sun. Light colours reflect significantly more heat. Testing has shown that dark colours can generate temperatures in excess of 85°C in direct sunlight whereas light colours under the same conditions can be as much as 35°C cooler. It is recommended that the chosen colour therefore has a Light Reflective Value greater than 45 (LRV of white is 95/100, LRV Black is 0).

14.0 Building maintenance

14.1 New construction

Building movement and settlement is inevitable. Paint coatings are affected by this occurrence whether it be concrete or timber substrate. It is important to deal immediately with new issues that are as a result of substrate movement – in the case of timber it is movement of the board. Make good these areas by priming and then touching up with the original, topcoat paint.

14.2 Regular washing

Exterior building surfaces benefit from being cleaned regularly. This is particularly important under eaves and overhangs. Mould, fungi and marine salts can have a detrimental effect on the paint coating and the substrate if left. Arrange to lightly wash all

surfaces at least annually. This is particularly important in a marine environment.

14.3 Maintenance painting

When required use a premium primer and undercoat, followed by the topcoat originally selected. In some circumstances where maintenance is delayed for many months it may be required to make good the repair area and then fully coat the whole section because of the change in the appearance of the coatings. Loss of gloss, colour change etc. is normal for paint.

Mostly walls facing north will be subject to this requirement, particularly if maintenance is delayed.

It is however, beneficial for both the paint film and the substrate to apply another coat. This maintenance should be viewed as a positive outcome for both the paint, the substrate and your investment in the home/building.

Building movement normally reduces over time. Experience has shown that areas that have been subject to maintenance in the main do not require further repairs providing the substrate is not subjected to continual movement.

As part of your maintenance, always check flashings, sealant and fastenings to ensure they do not permit the passage of water into the substrate. Left unchecked, water entry into the substrate can cause substantial damage which can become expensive to remedy.

Follow these instructions to ensure that your investment in A-lign natural solid timber products will stand the test of time.

For more information on A-lign call the Claymark Helpline on:

0800 25 44 61

Monday to Friday 8am–5pm

For more technical information and downloadable CAD and 3-D drawings, visit:

claymark.co.nz

A-align Warranty

Warranty

Claymark Limited ('Claymark Ltd') warrants for a period of 15 years from the date of purchase that its A-align cladding and A-align accessories (The 'Products'), will be free from production defects, and subject to compliance with the conditions below, will be resistant to cracking, rotting, and damage from borer attacks to the extent set out in Claymark Ltd's product literature current at the time of installation.

The A-align Technical Manual sets out the approved and recommended methods for cladding installation. A copy of the A-align Technical Manual is available from Claymark Ltd, phone toll free on: 0800 25 44 61 Monday to Friday 8am–5pm.

Conditions of Warranty

The warranty is strictly subject to the following conditions:

(a) The Products must be installed by a competent and qualified builder, strictly in accordance with the A-align Technical Manual current at the time of installation, utilising A-align components or products specified in the A-align Technical Manual. Where the A-align Technical Manual does not provide a suitable detail for installation of The Products then installation must be in accordance with best trade practice determined in consultation with the Territorial Authority and designer of the building works. Further, all other products, including coating and jointing systems, applied to or used in conjunction with The Products must be applied or installed strictly in accordance with the relevant manufacturer's instructions and best trade practice.

(b) Claymark Ltd will not be liable under this warranty unless a written claim is notified to Claymark Ltd within 30 days of the defect becoming reasonably apparent.

(c) This warranty is for the benefit of the original owner of the building where the A-align cladding has been installed. This warranty is not transferable to subsequent owners of the building.

(d) The Products must be maintained strictly in accordance with the A-align Technical Manual. Further, all other products, including coating and jointing systems, applied to or used in conjunction with The Products must be maintained strictly in accordance with the relevant manufacturer's instructions and best trade practice.

(e) The building works in which The Product has been incorporated must be designed and constructed in strict compliance with all relevant provisions of the current New Zealand Building Code ('NZBC'), regulations and standards, and the Building Consent relating to the building works.

(f) The customer's sole remedy under this warranty is (at Claymark Ltd's option) that Claymark Ltd will either supply replacement Products, rectify the affected Products or pay for the cost of the replacement or rectification of the affected Products.

(g) Claymark Ltd will not be liable for any losses or damages (whether direct or indirect) including property damage, personal injury, consequential loss, economic loss or loss of profits, arising in contract or negligence or howsoever arising. Without limiting the foregoing Claymark Ltd will not be liable for any claims, damages or defects arising from or in any way attributable to poor workmanship, poor design or detailing, settlement or structural movement and/or movement of materials to which The Products are attached, incorrect design off the structure, acts of God including but not limited to earthquakes, cyclones, floods or other severe weather conditions or unusual climatic conditions, efflorescence or performance of paint/coatings applied to The Products, normal wear and tear, growth of mould, mildew, fungi, bacteria, or any organism on the surface of any Products (whether on the exposed or unexposed surfaces).

(h) All warranties, conditions, liabilities and obligations other than those specified in this warranty are excluded to the fullest extent permitted by law. This warranty does not exclude or modify any legal rights a customer may have under the Consumer Guarantees Act 1993. Unless otherwise specified in writing at the time of sale, Claymark Ltd assumes no liability for The Products being fit for any particular purpose under the Building Act 2004, other legislation or at common law.

(i) If any remedial work undertaken under this warranty involves re-coating of The Products, the customer acknowledges and agrees that there may be slight colour differences between the original and replacement Products due to the effects of weathering and variations in materials over time.

Drawings Directory

Set out guides	17
Preparing a trimmed opening	20
Direct and cavity fixed – fixing guide	20

Direct fixed rusticated drawings	3-D	CAD
Figure 3.01 base of wall – concrete floor	21	30
Figure 3.02 base of wall – timber floor	21	30
Figure 3.03 eaves – angled soffit		31
Figure 3.04 eaves – flat soffit	21	31
Figure 3.05 eaves – no soffit	21	32
Figure 3.07 external corner – prefabricated box	21	32
Figure 3.08 external corner – mitred	21	33
Figure 3.09 internal corner – pre-cut scribe	22	33
Figure 3.10 internal corner – scribed	22	34
Figure 3.11 aluminium window – head	22	34
Figure 3.11a aluminium window – head	22	35
Figure 3.11b aluminium window – head		36
Figure 3.12 aluminium window – jamb	22	37
Figure 3.12a aluminium window – jamb		37
Figure 3.13 aluminium window – sill	22	38
Figure 3.13a aluminium window – sill	23	38
Figure 3.14 timber window – head	23	39
Figure 3.15 timber window – jamb	23	39
Figure 3.16 timber window – sill	23	40
Figure 3.17 meter box – head	23	40
Figure 3.17a meter box – jamb	23	
Figure 3.17b meter box – sill	24	
Figure 3.18 external corner – prefabricated box – stucco		41

	3-D	CAD
Figure 3.19 internal corner – pre-cut scribe – stucco		41
Figure 3.20 above stucco		42
Figure 3.21 external corner – prefabricated box – profiled metal		42
Figure 3.22 internal corner – pre-cut scribe – profiled metal		43
Figure 3.23 above profiled metal		43
Figure 3.24 below profiled metal		44
Figure 3.25 abutting profiled metal		44
Figure 3.26 external corner – masonry veneer		45
Figure 3.27 internal corner – masonry veneer		45
Figure 3.28 above masonry veneer		46
Figure 3.29 abutting masonry veneer		46
Figure 3.30 pipe penetration	24	47
Figure 3.31 above waterproof deck	24	47
Figure 3.32 reverse raked soffit		48
Figure 3.33 apron flashing		48
Figure 3.34 apron flashing – stop end	24	49
Figure 3.38 internal corner - 135 degrees - scribed		50
Figure 3.39 internal corner - 135 degrees - flashed		50
Figure 3.40 external corner - 135 degrees - mitred		51
Figure 3.41 nailing		51


Please note: All drawings are available
as downloadable files from our website:

claymark.co.nz


Cavity fixed rusticated drawings		3-D	CAD		3-D	CAD
Figure 4.01	base of wall – concrete floor	24	53	Figure 4.19	internal corner – pre-cut scribe – stucco	65
Figure 4.02	base of wall – timber floor		53	Figure 4.20	above stucco	66
Figure 4.03	eaves – angled soffit		54	Figure 4.21	external corner – prefabricated box – profiled metal	66
Figure 4.04	eaves – flat soffit	25	54	Figure 4.22	internal corner – pre-cut scribe – profiled metal	67
Figure 4.05	eaves – no soffit	25	55	Figure 4.23	above profiled metal	67
Figure 4.06	parapet – cap	25	55	Figure 4.24	below profiled metal	68
Figure 4.07	external corner – prefabricated box	25	56	Figure 4.25	abutting profiled metal	68
Figure 4.08	external corner – mitred	25	56	Figure 4.26	external corner – masonry veneer	69
Figure 4.09	internal corner – pre-cut scribe	25	57	Figure 4.27	internal corner – masonry veneer	69
Figure 4.10	internal corner – scribed	26	57	Figure 4.28	above masonry veneer	70
Figure 4.11	aluminium window – head	26	58	Figure 4.29	abutting masonry veneer	70
Figure 4.11a	aluminium window – head	26	59	Figure 4.30	pipe penetration	28 71
Figure 4.11b	aluminium window – head		60	Figure 4.31	above waterproof deck	28 71
Figure 4.12	aluminium window – jamb	26	61	Figure 4.32	reverse raked soffit	72
Figure 4.12a	aluminium window – jamb		61	Figure 4.33	apron flashing	72
Figure 4.13	aluminium window – sill	26	62	Figure 4.34	apron flashing – stop end	28 73
Figure 4.13a	aluminium window – sill	26	62	Figure 4.35	parapet – balustrade – wall junction	73
Figure 4.14	timber window – head	27	63	Figure 4.36	parapet – balustrade – saddle flashing	28 74
Figure 4.15	timber window – jamb	27	63	Figure 4.37	parapet – balustrade – saddle install	74
Figure 4.16	timber window – sill	27	64	Figure 4.38	horizontal cavity joint	28 75
Figure 4.17	meter box – head	27	64	Figure 4.39	internal corner - 135 degrees - scribed	75
Figure 4.17a	meter box – jamb	27		Figure 4.40	internal corner - 135 degrees - flashed	76
Figure 4.17b	meter box – sill	27		Figure 4.41	external corner - 135 degrees - mitred	76
Figure 4.18	external corner – prefabricated box – stucco		65	Figure 4.42	nailing	77



Set out Guide



A-align 142
Rusticated weatherboard



A-align 187
Rusticated weatherboard

Dimensions within brackets are rounded to millimetres.

A-align base weatherboard to finish min 50 mm below floor level (and 175 mm above finished ground level or 100 mm above paving)


— 3-Dimensional diagrams






Note: The 3-Dimensional diagrams and CAD drawings in this manual are current at the date of this manual (Sept 2018).
For any amendments or updates to these diagrams or drawings, please refer to our website: www.claymark.com/triptech/a-lign-nail-fix-cad-details


Preparing a trimmed opening – 1




Preparing a trimmed opening – 2




Preparing a trimmed opening – 3 (Direct fixed)



Preparing a trimmed opening – 4 (Direct fixed)



Direct fixed – fixing guide



Cavity fixed – fixing guide




Figure 3.01 Direct fixed –
base of wall – concrete floor




Figure 3.02 Direct fixed –
base of wall – timber floor




Figure 3.04 Direct fixed –
eaves – flat soffit




Figure 3.05 Direct fixed –
eaves – no soffit




Figure 3.07 Direct fixed –
external corner – prefabricated box




Figure 3.08 Direct fixed –
external corner – mitred




Figure 3.09 Direct fixed –
internal corner – pre-cut scribe




Figure 3.10 Direct fixed –
internal corner – scribed




Figure 3.11 Direct fixed –
aluminium window – head




Figure 3.11a Direct fixed –
aluminium window – head – jamb




Figure 3.12 Direct fixed –
aluminium window – jamb




Figure 3.13 Direct fixed –
aluminium window – sill




Figure 3.13a Direct fixed –
aluminium window – sill




Figure 3.14 Direct fixed –
timber window – head




Figure 3.15 Direct fixed –
timber window – jamb




Figure 3.16 Direct fixed –
timber window – sill




Figure 3.17 Direct fixed –
meter box – head




Figure 3.17a Direct fixed –
meter box – jamb




Figure 3.17b Direct fixed – meter box – sill




Figure 3.30 Direct fixed – pipe penetration




Figure 3.31 Direct fixed – above waterproof deck




Figure 3.34 Direct fixed – apron flashing – stop end




Figure 3.36 Direct fixed – parapet – balustrade – saddle flashing




Figure 4.01 Cavity fixed – base of wall – concrete floor




Figure 4.04 Cavity fixed –
eaves – flat soffit




Figure 4.06 Cavity fixed –
parapet – cap




Figure 4.08 Cavity fixed –
external corner – mitred




Figure 4.05 Cavity fixed –
eaves – no soffit




Figure 4.07 Cavity fixed –
external corner – prefabricated box




Figure 4.09 Cavity fixed –
internal corner – pre-cut scribe




Figure 4.10 Cavity fixed –
internal corner – scribed




Figure 4.11 Cavity fixed –
aluminium window – head




Figure 4.11a Cavity fixed –
aluminium window – head – jamb




Figure 4.12 Cavity fixed –
aluminium window – jamb




Figure 4.13 Cavity fixed –
aluminium window – sill




Figure 4.13a Cavity fixed –
aluminium window – jamb – sill




Figure 4.14 Cavity fixed –
timber window – head




Figure 4.15 Cavity fixed –
timber window – jamb




Figure 4.16 Cavity fixed –
timber window – sill




Figure 4.17 Cavity fixed –
meter box – head




Figure 4.17a Cavity fixed –
meter box – jamb




Figure 4.17b Cavity fixed –
meter box – sill




Figure 4.30 Cavity fixed – pipe penetration




Figure 4.31 Cavity fixed – above waterproof deck




Figure 4.34 Cavity fixed – apron flashing – stop end




Figure 4.36 Cavity fixed – parapet – balustrade – saddle flashing





Figure 4.38 Cavity fixed – horizontal cavity joint



— CAD drawings – direct fixed



Note: The 3-Dimensional diagrams and CAD drawings in this manual are current at the date of this manual (Sept 2018).
For any amendments or updates to these diagrams or drawings, please refer to our website: www.claymark.com/triptech/a-align-nail-fix-cad-details

Figure 3.01 Direct fixed – base of wall – concrete floor




Figure 3.02 Direct fixed – base of wall – timber floor




Figure 3.03 Direct fixed – eaves – angled soffit




Figure 3.04 Direct fixed – eaves – flat soffit




Figure 3.05 Direct fixed – eaves – no soffit




Figure 3.07 Direct fixed – external corner – prefabricated box




Figure 3.08 Direct fixed – external corner – mitred




Figure 3.09 Direct fixed – internal corner – pre-cut scribe




Figure 3.10 Direct fixed – internal corner – scribed






Figure 3.11 Direct fixed – aluminium window – head



Note: In wind zones Very High wind & above, sealant must be installed between the underside of the head flashing and top edge of window head flange – see E2/AS1 Fig 71(c).

Figure 3.11a Direct fixed – window head facing – option a



Note: In wind zones Very High wind & above, sealant must be installed between the underside of the head flashing and top edge of window head flange – see E2/AS1 Fig 71(c).

Elevation





Figure 3.11b Direct fixed – window head facing – option b



Note: In wind zones Very High wind & above, sealant must be installed between the underside of the head flashing and top edge of window head flange – see E2/AS1 Fig 71(c).

Elevation




Figure 3.12 Direct fixed – aluminium window – jamb




Figure 3.12a Direct fixed – aluminium window – jamb




Figure 3.13 Direct fixed – aluminium window – sill




Figure 3.13a Direct fixed – aluminium window – sill




Figure 3.14 Direct fixed – timber window – head




Figure 3.15 Direct fixed – timber window – jamb




Figure 3.16 Direct fixed – timber window – sill






Figure 3.17 Direct fixed – meter box



Note: Jamb detail similar to sill with angle to give cover to weatherboard with a A-align® pre-cut 27 x 18mm scribe.

Figure 3.18 Direct fixed – external corner – prefabricated box – stucco



Note: Run wall underlay continuously around internal and external corners - do not joint material at corner

Figure 3.19 Direct fixed – internal corner – pre-cut scribe – stucco




Figure 3.20 Direct fixed – above stucco




Figure 3.21 Direct fixed – external corner – prefabricated box – profiled metal




Figure 3.22 Direct fixed – internal corner – pre-cut scribe – profiled metal




Figure 3.23 Direct fixed – above profiled metal




Figure 3.24 Direct fixed – below profiled metal




Figure 3.25 Direct fixed – abutting profiled metal




Figure 3.26 Direct fixed – external corner – masonry veneer




Figure 3.27 Direct fixed – internal corner – masonry veneer




Figure 3.28 Direct fixed – above masonry veneer




Figure 3.29 Direct fixed – abutting masonry veneer




Figure 3.30 Direct fixed – pipe penetration




Figure 3.31 Direct fixed – above waterproof deck




Figure 3.32 Direct fixed – reverse raked soffit






Figure 3.33 Direct fixed – apron flashing



Note: Refer to NZBC Acceptable Solution E2/AS1 Table 7 for apron flashing cover over roofing

Figure 3.34 Direct fixed – apron flashing – stop end



Note: Refer to NZBC Acceptable Solution E2/AS1 Table 7 for apron flashing cover over roofing

Figure 3.38 Direct fixed – internal corner – 135 degrees – scribed




Figure 3.39 Direct fixed – internal corner – 135 degrees – flashed




Figure 3.40 Direct fixed – external corner – 135 degrees – mitred





Figure 3.41 Direct fixed – nailing





Note: The 3-Dimensional diagrams and CAD drawings in this manual are current at the date of this manual (Sept 2018). For any amendments or updates to these diagrams or drawings, please refer to our website: www.claymark.com/triptech/a-lign-nail-fix-cad-details

Figure 4.01 Cavity fixed – base of wall – concrete floor




Figure 4.02 Cavity fixed – base of wall – timber floor




Figure 4.03 Cavity fixed – eaves – angled soffit




Figure 4.04 Cavity fixed – eaves – flat soffit




Figure 4.05 Cavity fixed – eaves – no soffit





Figure 4.06 Cavity fixed – parapet – cap



Note: Install flexible flashing tape and saddle flashing at junction with full height wall

Figure 4.07 Cavity fixed – external corner – prefabricated box




Figure 4.08 Cavity fixed – external corner – mitred




Figure 4.09 Cavity fixed – internal corner – pre-cut scribe




Figure 4.10 Cavity fixed – internal corner – scribed






Figure 4.11 Cavity fixed – aluminium window – head



Note: In wind zones Very High wind & above, sealant must be installed between the underside of the head flashing and top edge of window head flange – see E2/AS1 Fig 71(c).

Figure 4.11a Cavity fixed – window head facing – option a



Note: In wind zones Very High wind & above, sealant must be installed between the underside of the head flashing and top edge of window head flange – see E2/AS1 Fig 71(c).

Elevation





Figure 4.11b Cavity fixed – window head facing – option b



Note: In wind zones Very High wind & above, sealant must be installed between the underside of the head flashing and top edge of window head flange – see E2/AS1 Fig 71(c).

Elevation




Figure 4.12 Cavity fixed – aluminium window – jamb




Figure 4.12a Cavity fixed – aluminium window – jamb




Figure 4.13 Cavity fixed – aluminium window – sill




Figure 4.13a Cavity fixed – aluminium window – sill




Figure 4.14 Cavity fixed – timber window – head




Figure 4.15 Cavity fixed – timber window – jamb




Figure 4.16 Cavity fixed – timber window – sill






Figure 4.17 Cavity fixed – meter box



Note: Jamb detail similar to sill with angle to give cover to weatherboard with a A-lign® pre-cut 27 x18mm scribe.

Figure 4.18 Cavity fixed – external corner – prefabricated box – stucco



Note: Run wall underlay continuously around internal and external corners - do not joint material at corners

Figure 4.19 Cavity fixed – internal corner – pre-cut scribe – stucco




Figure 4.20 Cavity fixed – above stucco




Figure 4.21 Cavity fixed – external corner – prefabricated box – profiled metal




Figure 4.22 Cavity fixed – internal corner – pre-cut scribe – profiled metal




Figure 4.23 Cavity fixed – above profiled metal




Figure 4.24 Cavity fixed – below profiled metal




Figure 4.25 Cavity fixed – abutting profiled metal




Figure 4.26 Cavity fixed – external corner – masonry veneer




Figure 4.27 Cavity fixed – internal corner – masonry veneer




Figure 4.28 Cavity fixed – above masonry veneer




Figure 4.29 Cavity fixed – abutting masonry veneer




Figure 4.30 Cavity fixed – pipe penetration




Figure 4.31 Cavity fixed – above waterproof deck




Figure 4.32 Cavity fixed – reverse raked soffit






Figure 4.33 Cavity fixed – apron flashing



Note: Refer to NZBC Acceptable Solution E2/AS1 Table 7 for apron flashing cover over roofing

Figure 4.34 Cavity fixed – apron flashing – stop end



Note: Refer to NZBC Acceptable Solution E2/AS1 Table 7 for apron flashing cover over roofing

Figure 4.35 Cavity fixed – parapet – balustrade – wall junction




Figure 4.36 Cavity fixed – parapet – balustrade – saddle flashing




Figure 4.37 Cavity fixed – parapet – balustrade – saddle install





Figure 4.38 Cavity fixed – horizontal cavity joint



Note: Horizontal drained joints must be provided for walls over 2-storeys in height in accordance with NZBC Acceptable Solution E2/AS1 paragraph 9.1.9.4(b)

Figure 4.39 Cavity fixed – internal corner - 135 degrees - scribed




Figure 4.40 Cavity fixed – internal corner - 135 degrees - flashed




Figure 4.41 Cavity fixed – external corner - 135 degrees - mitred





Figure 4.42 Cavity nailing



Claymark Limited

– Quality

Claymark quality assurance standards

To constantly deliver products that perform at the highest level demands excellent standards of quality in every area of business: from the training of our people, to product improvement, to concern for the environment.

We at Claymark Ltd are proud of our reputation for quality and integrity. A reputation that has been proven for generations. Our investment in quality is core to our company philosophy. Out of that dedication, innovation flows – and excellence continues year after year.

Our most recent certifications and standards are shown here. We will update these regularly. We strive to not just follow the strictest standards of our profession but to keep ahead of them. That way you, our customer, know that whenever you choose a product or service, you are choosing real quality.

Forest Stewardship Council® – chain of custody

Claymark Ltd has been independently certified by Scientific Certification Systems (SCS) in accordance with the rules of the Forest Stewardship Council® A.C. (FSC®).

SCS Certification Registration Number SCS-COC-000679

Timber Preservation Quality Manual. License Number 080

New Zealand Forest Industries Council

Claymark Ltd was awarded the champion training company for solid wood processing in 2001. The certificate was awarded by Forest Industries Training and Education Council.

Refer to www.claymark.co.nz for information on quality control methods.

For more information about our independent third party quality audit process contact us at:

0800 25 44 61

Monday to Friday 8am–5pm



©Claymark Group Ltd Partnership. All rights reserved. All intellectual property and images included in this Technical Manual and in the A-Align solutions are owned by Claymark Ltd and cannot be used without the express written consent of Timber Ltd. All applications for reproduction, in any form, should be made to Claymark Ltd. Claymark Ltd reserves the right to revise, without notice, any information contained in this document. Although every effort has been made to ensure the information contained in this document complies with existing standards and recognised good practice, no responsibility is accepted for any errors and omissions in this document, nor for any specifications or work based upon the information. Some of these images depict the A-Align solution and differ only slightly in size to the A-Align weatherboards and differ only slightly in size to the A-Align weatherboards and differ only slightly in size to the A-Align weatherboards which are not visible externally.

J003959 13/06/2023 June V-7.0



Ingrained Precision
in everything we do

claymark.co.nz